SR 316 at CR 3929 / WALTHER BLVD - GRADE SEPARATION
PI NO. 0010425
LEGEND
PROPOSED PAVEMENT
PROPOSED BRIDGE
SIDEWALK
GRASS
PROPERTY LINE
EXISTING R/W
ENVIRONMENTALLY SENSITIVE AREA
CONSTRUCTION LIMIT
PROPOSED R/W
LIMIT OF ACCESS R/W
EASEMENT
DRIVEWAY EASEMENT
EXISTING LIMIT OF ACCESS R/W
REMOVE EXISTING PAVEMENT
GEORGIA
DEPARTMENT
OF
TRANSPORTATION
SCALE IN FEET
0 50 100 200
TYPICAL SECTION
WALTHER BLVD.
12'-0" Shoulder
16'-0"
14'-0"
4'-0" Bike Lane
12'-0" Travel Lane
7'-0"
12'-0" Travel Lane
4'-0" Bike Lane
12'-0" Shoulder
5'-0" Sidewalk
2'-6"
Profile Grade
2%
0.11 MAX
6"
WALTHER BLVD.
SR 316 WESTBOUND
SR 316 EASTBOUND
ASCOT INVESTMENT COMPANY INC.
WILKINSON CGR LANDSCAPE LLC
MADISON AT RIVER GRAND EPTOD LLC
CRP POLLACK OAK LLC
SALEM GWINNETT PROPERTIES ASSOCIATES
NICHOLAS A. & EFFINIA FILIAMOS
ANN PROPERTIES, LLC
TREE CREEK BLVD.
PHILIP BLVD.
EXIST. R/W
EXIST. BLDG.
LAND LOT LINE 10
LAND LOT LINE 9
LAND LOT LINE 32
LAND LOT LINE 10
BEGIN CONSTRUCTION WALTHER BLVD. STA. 69+00.00
BEGIN PROJECT WALTHER BLVD. STA. 60+00.00
BEGIN REQ'D LIMITED ACCESS
END REQ'D LIMITED ACCESS
BEGIN BRIDGE STA. 72+02.00
END BRIDGE STA. 72+02.00
END PROJECT WALTHER BLVD. STA. 87+50.00
END CONSTRUCTION WALTHER BLVD. STA. 77+00.00
LIMIT OF CONSTRUCTION SR 316 STA. 1225+42.71
LIMIT OF CONSTRUCTION SR 316 STA. 1228+00.00
EXISTING PAVEMENT TO BE REMOVED
PC STA. 1234+58.65
PC STA. 1228+58.60
PC STA. 75+57.50
PC STA. 83+20.16
PC STA. 84+36.64
125+00
120+00
70+00
115+00
125+00